




Demarcation Sheet

Particulars	KHASRA NO.	AREA	REMARK
Phase -01	162,163,167, 169 & 171	11156.04. SQMT.	Demarcation with blue line (Tower-A1,A2 & D1) On going project
Phase -02	163,164, 165 & 167	7464.14 SQMT.	Demarcation with red line (Tower-A3,A4 & club) On going project
Phase -03	161 & 164	4302.30 SQMT.	Demarcation with green line (Tower-B1& B2) Proposed to be start
Phase -04	161&162	8472.05 SQMT.	Demarcation with magenta line (Tower-C1,C2 & D2) Proposed to be start
TOTAL AREA		31394.53 SQMT.	

AREA STATEMENT	
TOTAL PLOT AREA	= 31394.53 SQ.MT.
PLOT AREA UNDER COMMERCIAL	= 514.45 SQMT.
PLOT AREA UNDER FACILITIES	= 1646.08 SQMT.
TOTAL PLOT AREA UNDER COMMERCIAL/FACILITIES	= 2160.53 SQMT.
PLOT AREA UNDER RESIDENTIAL	= 29234.00 SQMT.
LAND LEFT FOR ROAD WIDENING UNDER RESIDENTIAL	= 288.60 SQ.MT.
LAND LEFT FOR ROAD WIDENING UNDER COMMERCIAL /FACILITIES	= 45.57 SQ.MT.
RESIDENTIAL	
NET PLOT AREA	= 28945.40 SQ.MT.
GREEN AREA (15.00%)	= 4341.81 SQMT.
PERMISSIBLE GROUND COVERAGE (40.00%)	= 11578.16 SQMT.
PERMISSIBLE F.A.R. (2.50)	= 72363.50 SQMT
INCENTIVE F.A.R. LIEU OF SHELTER FEES FOR EWS/LIG	= 4560.00 SQMT
TOTAL F.A.R.	= 76923.50 SQMT.
COVD. AREA ON BASEMENT	= 21548.28 SQMT.
COVD. AREA ON GR. COV. (INCLUDING LIFT AREA)	= 5522.42 SQMT. (19.08%)
OPEN AREA	= 23422.98 SQMT.
COVD. AREA ON GR. FL.	= 5522.46 SQMT.
COVD. AREA ON 1st. FL.	= 5112.46 SQMT.
COVD. AREA ON 2nd. FL.	= 5112.46 SQMT.
COVD. AREA ON 3rd. FL.	= 5112.46 SQMT.
COVD. AREA ON 4th. FL.	= 5112.46 SQMT.
COVD. AREA ON 5th. FL.	= 5112.46 SQMT.
COVD. AREA ON 6th. FL.	= 5112.46 SQMT.
COVD. AREA ON 7th. FL.	= 5112.46 SQMT.
COVD. AREA ON 8th. FL.	= 5112.46 SQMT.
COVD. AREA ON 9th. FL.	= 5112.46 SQMT.
COVD. AREA ON 10th. FL.	= 5112.46 SQMT.
COVD. AREA ON 11th. FL.	= 5112.46 SQMT.
COVD. AREA ON 12th. FL.	= 5112.46 SQMT.
COVD. AREA ON 13th. FL.	= 5112.46 SQMT.
COVD. AREA ON 14th. FL.	= 4760.74 SQMT.
TOTAL COVD. AREA	= 76745.18 SQMT.
F.A.R. = (2.65)	= 416.52 SQMT.
MUNTY & MECH RM. AREA	= 98709.98 SQMT.
TOTAL PROPOSED COVD. AREA	= 98709.98 SQMT.
CAR PARKING REQUIRED	= (254 X 1 + 432 X 1.25) = 254 + 540 = 794 No.S.
CAR PARKING PROVIDED IN BASEMENT	= 478 No.S.
TWO WHEELAR PARKING SPACE IN BASEMENT EQ TO	= 4108.4 SQMT.
CAR PARKING PROVIDED ON GROUND	= 128 ECS.
TOTAL CAR PARKING PROVIDED	= 220 No.S.
TOTAL No.S OF FLATS	= 826 No.S.
COMMERCIAL/FACILITIES	
PLOT AREA UNDER COMMERCIAL/FACILITIES	= 2160.53 SQMT.
LAND LEFT FOR ROAD WIDENING	= 45.57 SQ.MT.
NET PLOT AREA	= 2114.96 SQ.MT.
PERMISSIBLE GROUND COVERAGE (40.00%)	= 845.98 SQMT.
PERMISSIBLE F.A.R. (1.50)	= 3172.44 SQMT.
COVD. AREA ON G. FL.	= 63.19+685.21 = 748.40 SQMT. (35.39%)
OPEN AREA	= 1366.56 SQMT.
COVD. AREA ON 1st. FL.	= 748.40 SQMT.
TOTAL COVD. AREA	= 1496.80 SQMT.
F.A.R	= (0.71)
MUNTY AREA	= 19.15 SQMT.
CAR PARKING REQUIRED FOR SHOP & CLUB	= 1496.80X2/100 = 30 No.S.
TOTAL COVD. AREA	= 1515.95 SQMT.



S.NO.	KHASRA NO.	AREA
1	161	4100 SQMT.
2	162	4180 SQMT.
3	163	9320 SQMT.
4	164	9638 SQMT.
5	165 (PART)	403.10 SQMT.
6	167 (PART)	717.10 SQMT.
7	169	440 SQMT.
8	171 (PART)	2398.33 SQMT.
TOTAL AREA		31394.53 SQMT.

INCENTIVE FAR DETAIL	
TOTAL PLOT AREA	31394.53 SQ.MT.
PLOT AREA UNDER RESIDENTIAL	29234.00 SQMT.
LAND LEFT FOR ROAD WIDENING	288.60 SQ.MT.
NET PLOT AREA	28945.40 SQ.MT.
PERMISSIBLE UNITS (200/10000) = (28945.40X0.02)	578
TOTAL PERMISSIBLE UNITS	698
NO. OF EWS AS PER PERMISSIBLE UNITS(10%)	60.00
MINIMUM AREA OF EACH EWS UNIT	35 SQ.MT.
TOTAL INCENTIVE FAR IN LIEU OF EWS UNITS	2100.00
NO. OF LIG AS PER PERMISSIBLE UNITS(10%)	60.00
MINIMUM AREA OF EACH LIG UNIT	41 SQ.MT.
TOTAL INCENTIVE FAR IN LIEU OF LIG UNITS	2460.00
PERMISSIBLE F.A.R. (2.50)	72363.50 SQ.MT.
INCENTIVE F.A.R. LIEU OF SHELTER FEES FOR EWS/LIG	4560.00 SQ.MT.
TOTAL F.A.R.	76923.50 SQ.MT.

PROJECT:-
OMEGA
PROPOSED GROUP HOUSING BUILDING PLAN FOR OMEGA DEVELOPER AND BUILDERS ON KHASRA NO. 161, 162, 163, 164, 169, 165 (PART), 167(PART), & 171(PART) AT UTTARDHAUNA, FAIZABAD ROAD, LUCKNOW. (686 FLATS)

DRAWING TITLE :-
DEMARICATION PLAN

BUILDERS & PROMOTER :-
OMEGA DEVELOPER AND BUILDERS
Faizabad Rd, Lucknow, Uttar Pradesh 227105

DRAWN BY :-	CHECKED BY :-	DATED
RENU	YASOOB	
SCALE :-	DWG. NO.	JOB NO.
N.T.S.		

- THIS DRAWING IS THE PROPERTY OF SPACE DESIGNERS AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS ISSUED WITH OUT PERMISSION OF ITS PRINCIPALS.
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH OTHER RELEVANT ARCHITECTURAL, STRUCTURAL AND OTHER SERVICES/ CONSULTANTS DRAWING. IT SHALL BE THE DEEMED RESPONSIBILITY OF THE CONTRACTOR/ FABRICATOR TO BRING IN TO NOTICE OF ARCHITECTS IF ANY DISCREPANCY WITHIN OR BETWEEN THE DRAWINGS PRIOR TO CONSTRUCTION.
- ALL WRITTEN DIMENSIONS ARE TO BE FOLLOWED AND THE DRAWING IS NOT TO BE SCALED.

ARCHITECTS :-
Space Designers International
 B-34, Sector-67, Noida-201301 (U.P.)
 PH : 91-971653717,8,9,20
 e-mail : spacesdi@gmail.com, www.spacedi.com

THIS MAP HAS BEEN PREPARED UNDER MASTER PLAN 2031/BHAWANUPVIDHE 2008