AREA STATEMENT

Plot Area = 178.96 X 224.75		40,221.26	SQM.
Ground Coverage (Maximum Permissible) @ 30% of plot area		12,066.378	SQM.
Permissible FAR @ 2.75 of plot area		110,608.465	SQM. ---- (A)
Purchasable FAR @ 0.75 of plot area		30,165.945	SQM. ---- (B)
total FAR (2.75+0.75=3.5 of plot area)	=	140,774.410	SQM.
5% of Green building FAR at 3.5 FAR.	=	7,038.721	SQM. ---- (C)
Total permissible FAR. (A + B + C)	=	**147,813.13**	SQM.
Permissible Services @ 15% of 3.5 FAR	=	21,116.162	SQM.
Permissible commercial FAR @1% of 3.5 FAR	=	1,407.74	SQM.
Proposed Achieved FAR	=	**146249.610**	SQM.
Proposed Ground coverage (INCLUDIND GUARD RM.,METER RM & PANEL RM.)	=	**8,566.313**	SQM.
Proposed Services	=	**16,803.02**	SQM.
community facility area detail (FAR)			
A. Community Building	=	1490.431	SQM.
B. Community at 2nd floor of tower 10	=	711.965	SQM.
total (A + B)	=	**2202.396**	SQM.
proposed commercial FAR area detail			
A. commercial FAR at (GR. & 1ST floor of tower 10)	=	1098.445	SQM.
B. commercial FAR of restaurant (31th floor, tower no10)	=	228.129	SQM.
Total commercial FAR (A + B)	=	**1326.574**	SQM.
permissible density @ 1650 person / hectare	=	6636.5	PPL PERM.
total Achieved population	=	**6057**	person
PARKING CALCULATION			
required parking = perm. FAR/80 = 147813.13 / 80 = 1847.66 say	=	**1848**	**ECS . required**
proposed parking			
A. Parking in upper Basement	=	1017.9	ECS.
B. Parking in lower Basement	=	1044.3	ECS.
C. surface parking	=	66	ECS.
total proposed parking (A + B + C + D)	=	**2128.2**	**ECS. Provided**

Combine Area Detail

FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
FAR IN BSMT.-1	473.281	0	473.281	10.534	462.747	
GROUND FL.	8590.525	137.625	8452.9	332.750	8120.150	0
1ST FLOOR	7077.297	680.775	6396.522	424.083	5972.439	0
2nd FLOOR	6869.525	17.705	6851.82	482.674	6369.146	0
(SERVICE FL.)	513.036	17.705	495.331	0.000	0.000	495.331
3RD FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
4th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
5th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
6th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
7th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
8th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
9th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
10th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
11th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
12th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
13th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
14th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
15th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
16th FLOOR	6559.734	17.705	6542.029	483.627	6058.402	0
17th FLOOR	6545.884	17.705	6528.179	479.273	6048.906	0
18th FLOOR	6391.03	17.705	6373.325	479.273	5894.052	0
19th FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
20th FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
21st FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
22nd FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
23rd FLOOR	2979.187	17.705	2961.482	257.624	2703.858	0
24th FLOOR	2965.337	17.705	2947.632	253.270	2694.362	0
25th FLOOR	2810.483	17.705	2792.778	253.270	2539.508	0
26th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
27th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
28th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
29th FLOOR	2043.773	17.705	2026.068	165.340	1860.728	0
30th FLOOR	1396.107	17.705	1378.402	113.911	1264.491	0
31st FLOOR	1218.615	17.705	1200.91	109.511	1091.399	0
MUMTY/MCH.	970.686	0	970.686	970.686	0.000	0
Upper Bsmt.	35520.74	0	35520.74	1415.176	0	34105.564
Lower Bsmt.	35520.74	0	35520.74	2657.517	0	32863.223
METER ROOM	12.58	0	12.58	0	12.58	
PANEL ROOM	42.905	0	42.905	42.905	0	
GUARD ROOM	57.928	0	57.928	57.928	0	
TOTAL	**231884**	**1367.255**	**230516.747**	**16803.019**	**146249.610**	**67464.118**

FLOOR NAME	TOWER 1		TOWER -2		TOWER -3		TOWER -4		TOWER -5		TOWER -6		TOWER -7		TOWER -8		TOWER -9		TOWER -10	
	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS	UNITS	SR. UNITS
GROUND FL	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6		
1ST FL.	4	4					4	4			4	4					4	4		
2nd FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6		
3rd FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
4th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
5th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
6th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
7th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
8th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
9th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
10th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
11th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
12th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
13th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
14th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
15th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
16th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
17th FL.	6	6	2	2	2	2	6	6	2	2	6	6	2	2	2	2	6	6	8	
18th FL.	6	6					6	6	2	2	6	6	2	2	2	2	6	6	8	
19th FL.									2	2			2	2	2	2	6	6	8	
20th FL.									2	2			2	2	2	2	6	6	8	
21st FL.									2	2			2	2	2	2	6	6	8	
22nd FL.									2	2			2	2	2	2	6	6	8	
23rd FL.									2	2			2	2	2	2	6	6	8	
24th FL.									2	2			2	2	2	2	6	6	8	
25th FL.									2	2							6	6	8	
26th FL.									2	2							6	6	8	
27th FL.									2	2							6	6	8	
28th FL.									2	2							6	6	8	
29th FL.									2	2							6	6	8	
30th FL.																	6	6	8	
31st FL.																	6	6		
TOTAL	112		34		34		112		58		112		48		48		190		224	
TOTAL		112		34		34		112		58		112		48		48		190		

1A

2017/III-269/952

CAF/III/2024/HB-268/270
11-11-24

REVALIDATION
Map for proposed Building is as per Bye Laws. Submitted for Approval Please

Asstt/Arch. Architect

PERM POPULATION = 1650 PPL. / HAC.
PLOT AREA = 40,221.00 = 4.0221 HACTARE
= 6,636.47 PEOPLE

TOTAL UNITS = 972 DU.
TOTAL SR. UNITS = 748 DU.

PROPOSED POPULATION = 972 X 4.5 = 4374 PEOPLE
748 X 2.25 = 1683 PEOPLE
TOTAL = 6057 PEOPLE PROPOSRD

Map For Proposed Building is As Per Building Bye Laws Submitted For Approval Please.

Per Asstt. Asso. Arch Town Planner

24-1-2025
REVALIDATION
4/10 3/1/30

Tower - 1 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	1053.174		1053.174	34.856	1018.318	
3	1ST FLOOR	878.307		878.307	52.548	825.759	
4	2nd FLOOR	906.405		906.405	43.135	863.270	
5	(SERVICE FL.)						
6	3RD FLOOR	906.405		906.405	43.135	863.270	
7	4th FLOOR	906.405		906.405	43.135	863.270	
8	5th FLOOR	906.405		906.405	43.135	863.270	
9	6th FLOOR	906.405		906.405	43.135	863.270	
10	7th FLOOR	906.405		906.405	43.135	863.270	
11	8th FLOOR	906.405		906.405	43.135	863.270	
12	9th FLOOR	906.405		906.405	43.135	863.270	
13	10th FLOOR	906.405		906.405	43.135	863.270	
14	11th FLOOR	906.405		906.405	43.135	863.270	
15	12th FLOOR	906.405		906.405	43.135	863.270	
16	13th FLOOR	906.405		906.405	43.135	863.270	
17	14th FLOOR	906.405		906.405	43.135	863.270	
18	15th FLOOR	906.405		906.405	43.135	863.270	
19	16th FLOOR	906.405		906.405	43.135	863.270	
20	17th FLOOR	906.405		906.405	43.135	863.270	
21	18th FLOOR	906.405		906.405	43.135	863.270	
22	19th FLOOR						
23	20th FLOOR						
24	21st FLOOR						
25	22nd FLOOR						
26	23rd FLOOR						
27	24th FLOOR						
28	25th FLOOR						
29	26th FLOOR						
30	27th FLOOR						
31	28th FLOOR						
32	29th FLOOR						
33	30th FLOOR						
34	31st FLOOR						
35	MUMTY/MCH.	93.816		93.816	93.816		
36	TOTAL	17434.182		17434.182	914.515	16519.667	
37	TOTAL X T. NOS	17434.182	0.000	17434.182	914.515	16519.667	0.000

Tower No 2 &3 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	930.141		930.141	18.099	912.042	
3	1ST FLOOR	897.473		897.473	25.146	872.017	
4	2nd FLOOR	467.707		467.707	46.142	421.565	
5	(SERVICE FL.)						
6	3RD FLOOR	467.707		467.707	46.142	421.565	
7	4th FLOOR	467.707		467.707	46.142	421.565	
8	5th FLOOR	467.707		467.707	46.142	421.565	
9	6th FLOOR	467.707		467.707	46.142	421.565	
10	7th FLOOR	467.707		467.707	46.142	421.565	
11	8th FLOOR	467.707		467.707	46.142	421.565	
12	9th FLOOR	467.707		467.707	46.142	421.565	
13	10th FLOOR	467.707		467.707	46.142	421.565	
14	11th FLOOR	467.707		467.707	46.142	421.565	
15	12th FLOOR	467.707		467.707	46.142	421.565	
16	13th FLOOR	467.707		467.707	46.142	421.565	
17	14th FLOOR	467.707		467.707	46.142	421.565	
18	15th FLOOR	467.707		467.707	46.142	421.565	
19	16th FLOOR	467.707		467.707	46.142	421.565	
20	17th FLOOR	460.782		460.782	43.965	416.817	
21	18th FLOOR	383.355		383.355	43.965	339.39	
22	19th FLOOR						
23	20th FLOOR						
24	21st FLOOR						
25	22nd FLOOR						
26	23rd FLOOR						
27	24th FLOOR						
28	25th FLOOR						
29	26th FLOOR						
30	27th FLOOR						
31	28th FLOOR						
32	29th FLOOR						
33	30th FLOOR						
34	31st FLOOR						
35	MUMTY/MCH.	106.582		106.582	106.582		
36	TOTAL	8953.938		8953.938	930.777	8023.161	
37	TOTAL X T. NOS	17907.876	0	17907.876	1861.554	16046.322	0

Tower No- 4&6 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	994.585		994.585	64.165	930.420	
3	1ST FLOOR	798.324		798.324	54.873	743.451	
4	2nd FLOOR	869.364		869.364	45.292	824.072	
5	(SERVICE FL.)						
6	3RD FLOOR	869.364		869.364	45.292	824.072	
7	4th FLOOR	869.364		869.364	45.292	824.072	
8	5th FLOOR	869.364		869.364	45.292	824.072	
9	6th FLOOR	869.364		869.364	45.292	824.072	
10	7th FLOOR	869.364		869.364	45.292	824.072	
11	8th FLOOR	869.364		869.364	45.292	824.072	
12	9th FLOOR	869.364		869.364	45.292	824.072	
13	10th FLOOR	869.364		869.364	45.292	824.072	
14	11th FLOOR	869.364		869.364	45.292	824.072	
15	12th FLOOR	869.364		869.364	45.292	824.072	
16	13th FLOOR	869.364		869.364	45.292	824.072	
17	14th FLOOR	869.364		869.364	45.292	824.072	
18	15th FLOOR	869.364		869.364	45.292	824.072	
19	16th FLOOR	869.364		869.364	45.292	824.072	
20	17th FLOOR	869.364		869.364	45.292	824.072	
21	18th FLOOR	869.364		869.364	45.292	824.072	
22	19th FLOOR						
23	20th FLOOR						
24	21st FLOOR						
25	22nd FLOOR						
26	23rd FLOOR						
27	24th FLOOR						
28	25th FLOOR						
29	26th FLOOR						
30	27th FLOOR						
31	28th FLOOR						
32	29th FLOOR						
33	30th FLOOR						
34	31st FLOOR						
35	MUMTY/MCH.	93.816		93.816	93.816		
36	TOTAL	16665.913		16665.913	982.818	15683.095	
37	TOTAL X T. NOS	33331.826	0	33331.826	1965.636	31366.19	0

Tower No - 5 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	747.209		747.209	19.92	727.289	
3	1ST FLOOR	747.209	307.306	439.903	33.79	406.113	
4	2nd FLOOR	647.666		647.666	51.429	596.237	
5	(SERVICE FL.)						
6	3RD FLOOR	647.666		647.666	51.429	596.237	
7	4th FLOOR	647.666		647.666	51.429	596.237	
8	5th FLOOR	647.666		647.666	51.429	596.237	
9	6th FLOOR	647.666		647.666	51.429	596.237	
10	7th FLOOR	647.666		647.666	51.429	596.237	
11	8th FLOOR	647.666		647.666	51.429	596.237	
12	9th FLOOR	647.666		647.666	51.429	596.237	
13	10th FLOOR	647.666		647.666	51.429	596.237	
14	11th FLOOR	647.666		647.666	51.429	596.237	
15	12th FLOOR	647.666		647.666	51.429	596.237	
16	13th FLOOR	647.666		647.666	51.429	596.237	
17	14th FLOOR	647.666		647.666	51.429	596.237	
18	15th FLOOR	647.666		647.666	51.429	596.237	
19	16th FLOOR	647.666		647.666	51.429	596.237	
20	17th FLOOR	647.666		647.666	51.429	596.237	
21	18th FLOOR	647.666		647.666	51.429	596.237	
22	19th FLOOR	647.666		647.666	51.429	596.237	
23	20th FLOOR	647.666		647.666	51.429	596.237	
24	21st FLOOR	647.666		647.666	51.429	596.237	
25	22nd FLOOR	647.666		647.666	51.429	596.237	
26	23rd FLOOR	647.666		647.666	51.429	596.237	
27	24th FLOOR	647.666		647.666	51.429	596.237	
28	25th FLOOR	647.666		647.666	51.429	596.237	
29	26th FLOOR	647.666		647.666	51.429	596.237	
30	27th FLOOR	647.666		647.666	51.429	596.237	
31	28th FLOOR	647.666		647.666	51.429	596.237	
32	29th FLOOR	647.666		647.666	51.429	596.237	
33	30th FLOOR	647.666		647.666	51.429	596.237	
34	31st FLOOR						
35	MUMTY/MCH.	67.423		67.423	67.423		
36	TOTAL	19696.489	307.306	19389.183	1561.145	17828.038	
37	TOTAL X T. NOS	19696.489	307.306	19389.183	1561.145	17828.038	0

Tower No - 7 & 8 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	590.141		590.141	14.357	575.784	
3	1ST FLOOR	397.473		397.473	18.155	379.318	
4	2nd FLOOR	467.707		467.707	46.142	421.565	
5	(SERVICE FL.)						
6	3RD FLOOR	467.707		467.707	46.142	421.565	
7	4th FLOOR	467.707		467.707	46.142	421.565	
8	5th FLOOR	467.707		467.707	46.142	421.565	
9	6th FLOOR	467.707		467.707	46.142	421.565	
10	7th FLOOR	467.707		467.707	46.142	421.565	
11	8th FLOOR	467.707		467.707	46.142	421.565	
12	9th FLOOR	467.707		467.707	46.142	421.565	
13	10th FLOOR	467.707		467.707	46.142	421.565	
14	11th FLOOR	467.707		467.707	46.142	421.565	
15	12th FLOOR	467.707		467.707	46.142	421.565	
16	13th FLOOR	467.707		467.707	46.142	421.565	
17	14th FLOOR	467.707		467.707	46.142	421.565	
18	15th FLOOR	467.707		467.707	46.142	421.565	
19	16th FLOOR	467.707		467.707	46.142	421.565	
20	17th FLOOR	467.707		467.707	46.142	421.565	
21	18th FLOOR	467.707		467.707	46.142	421.565	
22	19th FLOOR						
23	20th FLOOR						
24	21st FLOOR						
25	22nd FLOOR						
26	23rd FLOOR						
27	24th FLOOR						
28	25th FLOOR						
29	26th FLOOR						
30	27th FLOOR						
31	28th FLOOR						
32	29th FLOOR						
33	30th FLOOR						
34	31st FLOOR						
35	MUMTY/MCH.	106.582		106.582	106.582		
36	TOTAL	12227.887		12227.89	1242.148	10985.739	
37	TOTAL X T. NOS	24455.774	0	24455.77	2484.296	21971.478	0

Tower No - 9 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	1053.174		1053.174	34.856	1018.318	
3	1ST FLOOR	878.307		878.307	52.548	825.759	
4	2nd FLOOR	906.405		906.405	43.135	863.270	
5	(SERVICE FL.)						
6	3RD FLOOR	906.405		906.405	43.135	863.270	
7	4th FLOOR	906.405		906.405	43.135	863.270	
8	5th FLOOR	906.405		906.405	43.135	863.270	
9	6th FLOOR	906.405		906.405	43.135	863.270	
10	7th FLOOR	906.405		906.405	43.135	863.270	
11	8th FLOOR	906.405		906.405	43.135	863.270	
12	9th FLOOR	906.405		906.405	43.135	863.270	
13	10th FLOOR	906.405		906.405	43.135	863.270	
14	11th FLOOR	906.405		906.405	43.135	863.270	
15	12th FLOOR	906.405		906.405	43.135	863.270	
16	13th FLOOR	906.405		906.405	43.135	863.270	
17	14th FLOOR	906.405		906.405	43.135	863.270	
18	15th FLOOR	906.405		906.405	43.135	863.270	
19	16th FLOOR	906.405		906.405	43.135	863.270	
20	17th FLOOR	906.405		906.405	43.135	863.270	
21	18th FLOOR	906.405		906.405	43.135	863.270	
22	19th FLOOR	906.405		906.405	43.135	863.270	
23	20th FLOOR	906.405		906.405	43.135	863.270	
24	21st FLOOR	906.405		906.405	43.135	863.270	
25	22nd FLOOR	906.405		906.405	43.135	863.270	
26	23rd FLOOR	906.405		906.405	43.135	863.270	
27	24th FLOOR	906.405		906.405	43.135	863.270	
28	25th FLOOR	906.405		906.405	43.135	863.270	
29	26th FLOOR	906.405		906.405	43.135	863.270	
30	27th FLOOR	906.405		906.405	43.135	863.270	
31	28th FLOOR	906.405		906.405	43.135	863.270	
32	29th FLOOR	906.405		906.405	43.135	863.270	
33	30th FLOOR	906.405		906.405	43.135	863.270	
34	31st FLOOR	906.405		906.405	43.135	863.270	
35	MUMTY/MCH.	93.816		93.816	93.816		
36	TOTAL	29217.447		29217.447	1475.27	27742.177	
37	TOTAL X T. NOS	29217.447		29217.447	1475.27	27742.177	0

Tower No - 10 Area Detail

SL. No.	FLOOR	ENVELOPE	CUTOUTS	COVD. AREA	SERVICES	FAR.	NON FAR
1	FAR IN BSMT. 1						
2	GROUND FL.	655.689	17.705	637.984	39.095	598.889	
3	1ST FLOOR	655.689	86.31	569.379	69.823	499.556	
4	2nd FLOOR	799.493	17.705	781.788	69.823	711.965	
5	(SERVICE FL.)	513.036	17.705	495.331			495.331
6	3RD FLOOR	489.702	17.705	471.997	70.776	401.221	
7	4th FLOOR	489.702	17.705	471.997	70.776	401.221	
8	5th FLOOR	489.702	17.705	471.997	70.776	401.221	
9	6th FLOOR	489.702	17.705	471.997	70.776	401.221	
10	7th FLOOR	489.702	17.705	471.997	70.776	401.221	
11	8th FLOOR	489.702	17.705	471.997	70.776	401.221	
12	9th FLOOR	489.702	17.705	471.997	70.776	401.221	
13	10th FLOOR	489.702	17.705	471.997	70.776	401.221	
14	11th FLOOR	489.702	17.705	471.997	70.776	401.221	
15	12th FLOOR	489.702	17.705	471.997	70.776	401.221	
16	13th FLOOR	489.702	17.705	471.997	70.776	401.221	
17	14th FLOOR	489.702	17.705	471.997	70.776	401.221	
18	15th FLOOR	489.702	17.705	471.997	70.776	401.221	
19	16th FLOOR	489.702	17.705	471.997	70.776	401.221	
20	17th FLOOR	489.702	17.705	471.997	70.776	401.221	
21	18th FLOOR	489.702	17.705	471.997	70.776	401.221	
22	19th FLOOR	489.702	17.705	471.997	70.776	401.221	
23	20th FLOOR	489.702	17.705	471.997	70.776	401.221	
24	21st FLOOR	489.702	17.705	471.997	70.776	401.221	
25	22nd FLOOR	489.702	17.705	471.997	70.776	401.221	
26	23rd FLOOR	489.702	17.705	471.997	70.776	401.221	
27	24th FLOOR	489.702	17.705	471.997	70.776	401.221	
28	25th FLOOR	489.702	17.705	471.997	70.776	401.221	
29	26th FLOOR	489.702	17.705	471.997	70.776	401.221	
30	27th FLOOR	489.702	17.705	471.997	70.776	401.221	
31	28th FLOOR	489.702	17.705	471.997	70.776	401.221	
32	29th FLOOR	489.702	17.705	471.997