- 29. Ensure use of measures for reducing water demand for landscaping and using xeriscaping, efficient irrigation equipments & controlled watering systems.
- 30. Make suitable provisions for using solar energy as alternative source of energy. Solar energy application should be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. Present a detailed report showing how much percentage of backup power for institution can be provided through solar energy so that use and polluting effects of DG sets can be minimized.
- 31. Make separate provision for segregation, collection, transport and disposal of e-waste.
- 32. Educate citizens and other stake-holders by putting up hoardings at different places to create environmental awareness.
- 33. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- 34. Prepare and present disaster management plan.
- 35. The project proponents shall ensure that no construction activity is undertaken without obtaining pre-environmental clearance.
- 36. A report on the energy conservation measures confirming to energy conservation norms finalize by Bureau of Energy efficiency should be prepared incorporating details about building materials and technology, R & U Factors etc.
- 37. Fly ash should be used as building material in the construction as per the provision of fly ash notification of September, 1999 and amended as on August, 2003 (The above condition is applicable only if the project lies within 100 km of Thermal Power Station).
- 38. The DG sets to be used during construction phase should use low sulphur liesel type and should conform to E.P. rules prescribed for air and noise emission standards.
- 39. Alternate technologies to Chlorination (for disinfection of waste water) including methods like Ultra Violet radiation, Ozonation etc. shall be examined and a report submitted with justification for selected technology.
- 40. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous variety.
- 41. The construction of the building and the consequent increased traffic load should be such that the micro climate of the area is not adversely affected.
- 42. The building should be designed so as to take sufficient safeguards regarding seismic zone sensitivity.
- 43. High rise buildings should obtain clearance from aviation department or concerned authority.
- 44. Suitable measures shall be taken to restrain the development of small or nmercial activities or slums in the vicinity of the complex. All commercial activities should be restricted to special areas earmarked for the purpose.
- 45. It is suggested that literacy program for weaker sections of society/women/adults (including domestic help) and under privileged children could be provided in a formal way.
- 46. The use of Compact Fluorescent lamps should be encouraged. A management plan for the safe disposal of used/damaged CFLs should be submitted.
- 47. it shall be ensured that all Street and park lighting is solar powered. 50 % of the same may be provided with dual (solar/electrical) alternatives.
- 48. Solar water heater shall be installed to the maximum possible capacity. Plans may be drawn up accordingly ad submitted with justification.
- 49. Treated effluents shall be maximally reused to aim for zero discharge. Where ever not possible, a detailed management plan for disposal should be provided with quantities and quality of waste water.
- 50. The treated effluents should normally not be discharged into public sewers with terminal treatment facilities as they adversely affect the hydraulic capacity of STP. If unable, necessary permission from authorities should be taken.
- 51. Construction activities including movements of vehicles should be so managed so that no disturbance is caused to nearby residents.
- 52. All necessary statutory clearances should be obtained and submitted before start of any construction activity and if this condition is violated the clearance, if and when given, shall be automatically deemed to have been cancelled.