

Uploaded on
www.seiaaup.in

To,

**Shri Peeyush chaudhry,
V.P. Architecture,
M/s Logix Height Pvt. Ltd,
The Corenthum, Tower-B,
IVth floor, Office No- 44,
Plot no- A-41, Sector-62,
Noida, U.P- 201301**

Ref. No. 383 /Parya/SEAC/3679/2016

Date: 22/03/ , 2017

Sub: Revision in the Environmental Clearance for "Group Housing Project" at Plot No.SC-01/A-3, Sector -150, Noida, U.P. M/s Logix Heights Pvt.Ltd, Regarding.

Dear Sir,

Please refer to your application/letters 14-05-2016, 19-11-2016 & 22-12-2016 addressed to the Secretary, State Level Expert Appraisal Committee (SEAC) and Director, Directorate of Environment Govt. of UP on the subject as above. A presentation was made by the representative of the project proponent along with their consultant M/s Perfect Enviro Solutions Pvt. Ltd in the SEAC meeting dated 26/12/2016.

The Project proponent, through documents (submitted to SEAC) and presentation made during meeting, has informed to the SEAC that:-

1. The environmental clearance is sought for "Group Housing Project" at Plot No.SC-01/A-3, Sector -150, Noida, U.P. M/s Logix Heights Pvt.Ltd.
2. The land is allotted by Noida Industrial Development Authority to M/s Logix Heights Pvt. Ltd. The Environmental Clearance has already been granted vide letter no. letter no. 1767/Parya/SEAC/1881/2013/DDY Dated 11/10/2013 to the project for plot area 28,326.34 sqm and built up area 79,147.37 Sqm.
3. Due to change in planning, as per approved building plan and revision in FAR, built-up-area of the project changes from 79,147.34 sq m to 75,041.964 sq m.
4. The proposed project will have dwelling units, Villas, Commercial Building & Community Hall.
5. Project Details:

S. No.	Details	As per Environmental Clearance	Revised Project Details	Impact
1.	Total Plot area	28326.34 sqm	28326.34 sqm	-
2.	Cost of project	-	260 crores	-
3.	Ground coverage Permissible	7931.36 sqm (27.9%)	7931.36 sqm (27.9%)	-
4.	Ground coverage proposed	5825 sqm (20.6%)	7150.393 sqm (25.2%)	Increase- 1325.393 sqm
5.	FAR Residential (Permissible)	45000 sqm (159%)	45000 sqm (159%)	-
	Additional Green 5% FAR	2250	2250	-
	Total Permissible FAR	47250 sqm	47250 sqm	-
6.	FAR (proposed) Residential	47249.8 Sqm (167%)	47112.378 Sqm (166%)	Decrease- 137.422 sqm
7.	Permissible Services Area	7087.5	6750	Decrease- 337.5 sqm
	Proposed Services Area	6992.970 sqm	6634.995 sqm	Decrease- 357.975 sqm
8.	Basement area	19930.35	19930.35 Sqm	No change
9.	Number of Basement	1.	1	-



10.	Non-FAR(Stilt)	1697 Sqm	1364.241 Sqm	decrease-332.759 sqm
11.	Non-FAR(Other)	3277.22	-	-
12.	Total Built-up area(FAR, Non-FAR, Basement)	79147.34 Sqm	75041.964 Sqm	Decrease-4105.376 sqm
13.	Green Area	11681.09 Sqm (41.23%)	12779.485 Sqm (45.1%)	Increase-1098.395 sqm
15.	No. of floors	B+S+25	B+S+22	Decrease
16.	Height of building	45m	80.30m	Increase-35.3m
17.	No. of Dwelling Unit	300+8 Vilas	308+28 Vilas	Increase-28
18.	Population			
	Residents	1386	1512	Increase-126
	Staff	50	50	-
	Visitors	150	150	-
	Total population	1586	1712	Increase-126
19.	Total Power Load	2000 KW	2021 KW	Increase-21 KW
20.	No. of DG sets	2 X 1000 KVA & 1 X 750 KVA	2 X 1010 KVA	Decrease
21.	No. of Rainwater Harvesting pits	9	6	Decrease
22.	Parking required	590 for residents + 60 for visitors - 650	591 for residents + 60 for visitors = 651	Increase-1 ECS
23.	Parking proposed	620	657	Increase-37 ECS
24.	Water requirement	180 KLD	184 KLD	Increase-4 KLD
25.	STP capacity	150 KLD	170 KLD	Increase-20 KLD
26.	Solid waste generated	724.77 kg/day	814 kg/day	Increase-89.23 kg/day

6. Land use Details:

LAND USE AS PER EC GRANTED		
Land Use	Area in sqm	Percentage
Ground Coverage	5825	20.6
Green Area	11681.09	41.23
Open and Road Area	10820.25	38.17
Total	28326.34 sqm	100%
LAND USE AFTER REVISION		
Land Use	Area in sqm	Percentage
Ground Coverage	7150.393	25.2
Green Area	12779.485	45.1
Open and Road Area	8396.462	29.7
Total	28326.34 sqm	100%

7. Water Management:

S.No.	Particulars	Population	Factor in LPCD	TOTAL requirement(KLD)	Waste Water(KLD)
1	Resident (DU +Villas)	1708	86	147	
2	Staff	50	45	2	
3	Visitors	150	15	3	
4	Sub Total	1908		152	131
				Domestic: 106 KLD Flushing: 46 KLD	Domestic: 85 KLD Flushing: 46 KLD



Pvt.Ltd.

5	Gardening			13	nil
6	DG Cooling			12	nil
7	Misc.			5	4
8	Swimming Pool			2	nil
	Total			184 KLD	135 KLD

8. Rain Water Harvesting:

Soil Quality	:	Silt Loam
Porosity	:	35 %
Infiltration rate	:	15.2 mm/ hr
Ground Water Level	:	18 m
Annual Rain fall	:	723 mm
Peak Hourly Rain	:	45 mm/hr
No. of rain water harvesting pits	:	6 no (3 no circular and 3 no rectangular)
Size of each pit(rectangular)	:	6 m x 3.0 m x 3.7 m
Size of each pit (circular)	:	Dia 3.0 m depth 3.5 m

S.No.	Type of surface	Catchment area (Sq. m)	Runoff coefficient	Intensity of rainfall (mm/hr) Peak hourly 45 mm	Water Discharge (runoff) (in cu m)
1.	Roof top area	7150.393	0.85	15	91 cum

9. status of construction :-

TOWER	TOTAL AREA					ALREADY COMPLETED					PROPOSED	
	Built-up AREA (sq m)	FAR AREA	NON FAR AREA	TOTAL DU	NO OF FLOORS	Floors as per EC	units as per EC	CONSTRUCTED FLOORS	Built-up AREA (sq m)	UNITS CONSTRUCTED	UNITS TO BE CONSTRUCTED	AREA TO BE CONSTRUCTED (sq m)
Basement	1993.035								1993.035			
T1	2462.2111	2158.656	3035.551	132	G+2	G+25	150	G+8	9,066.11	48	84	15,556.00
T2	1900.9456	1695.9078	2050.378	176	G+2	G+25	200	G+8	6,962.36	64	112	12,047.10
Villas	9750.356	8566.74	1183.616	28	G+2	G+2	8	6 Villas	1,835.73	6	22	7,914.63
Stilt	1364.241		1364.241									
Community	365.45		365.45									
TOTAL	7504.1964	4711.2378	7999.236	336					3779.4546	118	218	35517.727
BUILT UP AREA												

10. The project proposals are covered under category 8(a) of EIA Notification, 2006.

Based on the recommendations of the State Level Expert Appraisal Committee Meeting (SEAC) held on 26/12/2016 the State Level Environment Impact Assessment Authority (SEIAA) in its Meeting held on




13/02/2017 decided to grant the Environmental Clearance for proposed project along with subject to the effective implementation of the following general and specific conditions:-

General Conditions:

1. It shall be ensured that all standards related to ambient environmental quality and the emission/effluent standards as prescribed by the MoEF are strictly complied with.
2. It shall be ensured that obtain the no objection certificate from the U P pollution control board before start of construction.
3. It shall be ensured that no construction work or preparation of land by the project management except for securing the land is started on the project or the activity without the prior environmental clearance.
4. The proposed land use shall be in accordance to the prescribed land use. A land use certificate issued by the competent Authority shall be obtained in this regards.
5. All trees felling in the project area shall be as permitted by the forest department under the prescribed rules. Suitable clearance in this regard shall be obtained from the competent Authority.
6. Impact of drainage pattern on environment should be provided.
7. Surface hydrology and water regime of the project area within 10 km should be provided.
8. A suitable plan for providing shelter, light and fuel, water and waste disposal for construction labour during the construction phase shall be provided along with the number of proposed workers.
9. Measures shall be undertaken to recycle and reuse treated effluents for horticulture and plantation. A suitable plan for waste water recycling shall be submitted.
10. Obtain proper permission from competent authorities regarding enhanced traffic during and due to construction and operation of project.
11. Obtain necessary clearances from the competent Authority on the abstraction and use of ground water during the construction and operation phases.
12. Hazardous/inflammable/Explosive materials likely to be stored during the construction and operation phases shall be as per standard procedure as prescribed under law, Necessary clearances in this regards shall be obtained.
13. Solid wastes shall be suitably segregated and disposed. A separate and isolated municipal waste collection center should be provided. Necessary plans should be submitted in this regards.
14. Suitable rainwater harvesting systems as per designs of groundwater department shall be installed. Complete proposals in this regard should be submitted.
15. The emissions and effluents etc. from machines, Instruments and transport during construction and operation phases should be according to the prescribed standards. Necessary plans in this regard shall be submitted.
16. Water sprinklers and other dust control measures should be undertaken to take care of dust generated during the construction and operation phases. Necessary plans in this regard shall be submitted.
17. Suitable noise abatement measures shall be adopted during the construction and operation phases in order to ensure that the noise emissions do not violate the prescribed ambient noise standards. Necessary plans in this regard shall be submitted.
18. Separate stock piles shall be maintained for excavated top soil and the top soil should be utilized for preparation of green belt.
19. Sewage effluents shall be kept separate from rain water collection and storage system and separately disposed. Other effluents should not be allowed to mix with domestic effluents.
20. Hazardous/Solid wastes generated during construction and operation phases should be disposed off as prescribed under law. Necessary clearances in this regard shall be obtained.
21. Alternate technologies for solid waste disposals (like vermin-culture etc.) should be used in consultation with expert organizations.
22. No wetland should be infringed during construction and operation phases. Any wetland coming in the project area should be suitably rejuvenated and conserved.
23. Pavements shall be so constructed as to allow infiltration of surface run-off of rain water. Fully impermeable pavements shall not be constructed. Construction of pavements around trees shall be as per scientifically accepted principles in order to provide suitable watering, aeration and nutrition to the tree.
24. The Green building Concept suggested by Indian Green Building Council, which is a part of CII-Godrej GBC, shall be studied and followed as for as possible.



25. Compliance with the safety procedures, norms and guidelines as outlined in National Building Code 2005 shall be compulsorily ensured.
26. Ensure usage of dual flush systems for flush cisterns and explore options to use sensor based fixtures, waterless urinals and other water saving techniques.
27. Explore options for use of dual pipe plumbing for use of water with different qualities such as municipal supply, recycled water, ground water etc.
28. Ensure use of measures for reducing water demand for landscaping and using xeriscaping, efficient irrigation equipments & controlled watering systems.
29. Make suitable provisions for using solar energy as alternative source of energy. Solar energy application should be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. Present a detailed report showing how much percentage of backup power for institution can be provided through solar energy so that use and polluting effects of DG sets can be minimized.
30. Make separate provision for segregation, collection, transport and disposal of e-waste.
31. Educate citizens and other stake-holders by putting up hoardings at different places to create environmental awareness.
32. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
33. Prepare and present disaster management plan.
34. The project proponents shall ensure that no construction activity is undertaken without obtaining pre-environmental clearance.
35. A report on the energy conservation measures conforming to energy conservation norms finalize by Bureau of Energy efficiency should be prepared incorporating details about building materials and technology, R & U Factors etc.
36. Fly ash should be used as building material in the construction as per the provision of fly ash notification of September, 1999 and amended as on August, 2003 (The above condition is applicable only if the project lies within 100 km of Thermal Power Station).
37. The DG sets to be used during construction phase should use low sulphur diesel type and should conform to E.P. rules prescribed for air and noise emission standards.
38. Alternate technologies to Chlorination (for disinfection of waste water) including methods like Ultra Violet radiation, Ozonation etc. shall be examined and a report submitted with justification for selected technology.
39. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous variety.
40. The construction of the building and the consequent increased traffic load should be such that the micro climate of the area is not adversely affected.
41. The building should be designed so as to take sufficient safeguards regarding seismic zone sensitivity.
42. High rise buildings should obtain clearance from aviation department or concerned authority.
43. Suitable measures shall be taken to restrain the development of small commercial activities or slums in the vicinity of the complex. All commercial activities should be restricted to special areas earmarked for the purpose.
44. It is suggested that literacy program for weaker sections of society/women/adults (including domestic help) and under privileged children could be provided in a formal way.
45. The use of Compact Fluorescent lamps should be encouraged. A management plan for the safe disposal of used/damaged CFLs should be submitted.
46. It shall be ensured that all Street and park lighting is solar powered. 50% of the same may be provided with dual (solar/electrical) alternatives.
47. Solar water heater shall be installed to the maximum possible capacity. Plans may be drawn up accordingly and submitted with justification.
48. Treated effluents shall be maximally reused to aim for zero discharge. Where ever not possible, a detailed management plan for disposal should be provided with quantities and quality of waste water.
49. The treated effluents should normally not be discharged into public sewers with terminal treatment facilities as they adversely affect the hydraulic capacity of STP. If unable, necessary permission from authorities should be taken.



50. Construction activities including movements of vehicles should be so managed so that no disturbance is caused to nearby residents.
51. All necessary statutory clearances should be obtained and submitted before start of any construction activity and if this condition is violated the clearance, if and when given, shall be automatically deemed to have been cancelled.
52. Parking areas should be in accordance with the norms of MOEF, Government of India. Plans may be drawn up accordingly and submitted.
53. The location of the STP should be such that it is away from human habitation and does not cause problem of odor. Odorless technology options should be examined and a report submitted.
54. The Environment Management plan should also include the break up costs on various activities and the management issues also so that the residents also participate in the implementation of the environment management plan.
55. Detailed plans for safe disposal of STP sludge shall be provided along with ultimate disposal location, quantitative estimates and measures proposed.
56. Status of the project as on date shall be submitted along with photographs from North, South, West and East side facing camera and adjoining areas should be provided.
57. Specific location along with dimensions with reference to STP, Parking, Open areas and Green belt etc. should be provided on the layout plan.
58. The DG sets shall be so installed so as to conform to prescribed stack heights and regulations and also to the noise standards as prescribed. Details should be submitted.
59. E-Waste Management should be done as per MoEF guidelines.
60. Electrical waste should be segregated & disposed suitably as not to impose Environmental Risk.
61. The use of suitably processed plastic waste in the construction of roads should be considered.
62. Displaced persons shall be suitably rehabilitated as per prescribed norms.
63. Dispensary for first aid shall be provided.
64. Safe disposal arrangement of used toiletries items in Hotels should be ensured. Toiletries items could be given complementary to guests, adopting suitable measures.
65. Diesel generating set stacks should be monitored for CO and HC.
66. Ground Water downstream of Rain Water Harvesting pit nearest to STP should be monitored for bacterial contamination. Necessary Hand Pumps should be provided for sampling. The monitoring is to be done both in pre and post monsoon, seasons.
67. The green belt shall consist of 50% trees, 25% shrubs and 25% grass as per MoEF norms.
68. A Separate electric meter shall be provided to monitor consumption of energy for the operation of sewage/effluent treatment in tanks.
69. An energy audit should be annually carried out during the operational phase and submitted to the authority.
70. Project proponents shall endeavor to obtain ISO: 14001 certification. All general and specific conditions mentioned under this environmental clearance should be included in the environmental manual to be prepared for the certification purposes and compliance.
71. Environmental Corporate Responsibility (ECR) plan along with budgetary provision amounting to 2% of total project cost shall be submitted (within the month) on need base assessment study in the study area. Income generating measures which can help in up-liftment of weaker section of society consistent with the traditional skills of the people identified. The program me can include activities such as old age homes, rain water harvesting provisions in nearby areas, development of fodder farm, fruit bearing orchards, vocational training etc. In addition, vocational training for individuals shall be imparted so that poor section of society can take up self employment and jobs. Separate budget for community development activities and income generating programmers shall be specified. Revised ECR plan is to be submitted within 3 month. Failing which, the environmental Clearance shall be deemed to be cancelled.
72. Appropriate safety measures should be made for accidental fire.
73. Smoke meters should be installed as warning measures for accidental fires.
74. Plan for safe disposal of R.O reject is to be submitted.

SPECIFIC CONDITIONS:

1. Provision of parking should be restricted to ECS as required under Development Authority bye-laws.
2. Provision of setback on all sides should be made as per Development Authority bye-laws.
3. Copy of all NOCs from different departments shall be obtained prior to start of construction.



4. Necessary planning for any anticipated expansion should be incorporated in present design in view of structural stability.
5. An underground water reservoir shall be planned within the premises for storage of rain water.
6. Municipal solid waste shall be disposed/managed as per Municipal Solid Waste (Management and Handling) Rules, 2000 (as amended).
7. 15% area of the total plot area shall be compulsorily made available for the green belt development including the peripheral green belt.
8. Project falling within in norm area of Wild Life Sanctuary is to obtain a clearance from National Board Wild Life (NBWL) even if the eco- sensitive zone is not earmarked.
9. Criteria/ norms provided by competent Authority regarding the seismic zone be followed for construction work. Provision of alarm system, to timely notify the residents, in case of occurrence of earthquake/other natural disasters/fire should be provided. A well defined evacuation plan should also be prepared and regular mock drills should be arranged for the residents. Rise of stairs should be constructed in a way, so that it should provide smooth movement.
10. For the treatment for total sewage, a full-fledged STP is to be provided with 20% more capacity than waste water generated during operation phase.100% waste water is to be treated in captive STP conforming to prescribed standards of receiving body for designated use. Monitoring of STP to be done daily till its stabilization.
11. Dual plumbing should be adopted. Recycling of water as proposed shall be undertaken with regular testing and monitoring of treated water.
12. Dedicated power supply for STPs is to be ensured during operation. Sludge of STP is to be used in-house as manure and surplus manure should be managed by giving it to end users. STP shall be suitably located nearest to back side boundary with shortest out let. Operation and the maintenance cost of the STP shall also be informed along with the compliance of the E-waste and municipal solid waste disposal.
13. Corporate Social Responsibility (CSR) plan along with budgetary provision amounting to 2% of the total project cost shall be prepared and approved by Board of Directors of the company. A copy of resolution as above shall be submitted to the authority. A list of beneficiaries with their mobile nos./address should be submitted alongwith six monthly compliance reports.
14. LEDs should be used in all common areas and corridors. 100% solar lighting is to be provided in the open areas/ stairs cases.
15. All entry/exit point should be bell mouth shaped.
16. To discharge excess treated waste water into public drainage system, permission from the competent authority to be taken prior to any discharge.
17. 100 % provision of Rain Water Harvesting is to be made. RWH shall be initially done only from the roof top. RWH from green and other open areas shall be done only after permission from CGWB.
18. Height of the stack should be provided based on combined DG sets capacity and be 6 mt higher than the tallest building. Necessary permission should be sought prior to operation of DG sets.
19. Post project monitoring for air, water (surface + ground), Stack noise of D.G. sets, STP to be carried out as CPCB Guidelines.
20. Crèche to be provided during the construction/operation phase.
21. LIG & EWS housing to be provided as per U.P. Govt. Orders and building bye laws.
22. Provision of separate room for senior citizen with proper amenities shall be made.
23. Protection shall be provided on the windows of the high rise flats for security of residents.
24. Unless and until all the environmental issues are sorted out the occupancy will be restricted and would be only allowed after achieving the Permission from the competent authority.
25. The project proponent shall ensure that the project site does not attract/infringe any buffer zone of no activity identified/declared under law.
26. For any extraction of ground water, prior permission from CGWB shall be taken.
27. Sprinkler to be used for curing and quenching and ready mix concrete may be used for construction.
28. Possibilities of use of treated waste water for irrigation purposes should be explored. Drip irrigation should be tried upto extent possible. No fresh water will be used for irrigation purpose.
29. Mobile toilets, safe drinking water facility, sanitation facility and eco friendly fuels etc. Shall be made available to the temporary residents/workers at the project site including the proper treatment and the disposal of the wastes.

No construction/operation is to be started without obtaining Prior Environmental Clearance.

Concealing factual data and information or submission of false/fabricated data and failure to comply with any of the conditions stipulated in the Prior Environmental Clearance attract action under the provision of Environmental (Protection) Act, 1986.

This Environmental Clearance is subject to ownership of the site by the project proponents in confirmation with approved Master Plan for G.B. Nagar. In case of violation, it would not be effective and would automatically be stand cancelled.

You are also directed to ensure that the proposed site is not a part of any no-development zone as required/prescribed/identified under law. In case of violation, this permission shall automatically deem to be cancelled. Also, in the event of any dispute on ownership or land use of the proposed site, this clearance shall automatically deemed to be cancelled.

The project proponent will have to submit approved plans and proposals incorporating the conditions specified in the Environmental Clearance within 03 months of issue of the clearance. The SEIAA/MoEF reserves the right to revoke the environmental clearance, if conditions stipulated are not implemented to the satisfaction of SEIAA/MoEF. SEIAA may impose additional environmental conditions or modify the existing ones, if necessary. Necessary statutory clearances should be obtained and submitted before start of any construction activity.

These stipulations would be enforced among others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006 including the amendments and rules made thereafter.

This is to request you to take further necessary action in the matter as per provision of Gazette Notification No. S.O. 1533(E) dated 14.9.2006, as amended and send regular compliance reports to the authority as prescribed in the aforesaid notification.




No..... /Parya/SEAC/3679/2016

Dated: As above

Copy with enclosure for information and necessary action to:

1. The Principal Secretary, Department of Environment, Govt. of Uttar Pradesh, Lucknow.
2. Advisor, IA Division, Ministry of Environment, Forests & Climate Change, Govt. of India, Indira Paryavaran Bhawan, Jor Bagh Road, Aliganj, New Delhi.
3. Chief Conservator, Regional Office, Ministry of Environment & Forests, (Central Region), Kendriya Bhawan, 5th Floor, Sector-H, Aliganj, Lucknow.
4. District Magistrate, G.B. Nagar.
5. The Member Secretary, U.P. Pollution Control Board, TC-12V, Paryavaran Bhawan, Vibhuti Khand, Gomti Nagar, Lucknow.
6. Regional Officers, Regional Office, UP Pollution Control Board, Noida.
7. Copy to Web Master/ guard file.


(Shruti Shukla)
Deputy Director,
Directorate of Environment, U.P.