

Electrical Load Calculation - Nirala Greenshire				
Summary of Load sheet for Substation-01, for Part Completion of Towers - G6 to G14)				
S. No	DESCRIPTION	Nos of Units	Total Load	
Normal Electrical Load				
i)	Substation -01 (Tower - G6, G7, G8, G9, G10, G11, G12 & G14)	1132	3,170	KVA
	Total	1132	3,170	KVA
Selection of Transformer				
For Substation -01 : - 2 nos. 2000 KVA each.				
Essential Electrical Load				
i)	Substation -01 (Tower - G6, G7, G8, G9, G10, G11, G12 & G14)	1132	2,237	KVA
	Total	1132	2,237	KVA

