

50. Construction activities should be managed so that no disturbance is caused to nearby residents.

51. All necessary statutory clearances should be obtained and submitted before start of any construction activity and if this condition is violated the clearance, if and when given, shall be automatically deemed to have been cancelled.

52. Parking areas should be in accordance with the norms of MOEF, Government of India. Plans may be drawn up accordingly and submitted.

53. The location of the STP should be such that it is away from human habitation and does not cause problem of odor. Odorless technology options should be examined and a report submitted.

54. The Environment Management plan should also include the break up costs on various activities and the management issues also so that the residents also participate in the implementation of the environment management plan.

55. Detailed plans for safe disposal of STP sludge shall be provided along with ultimate disposal location, quantitative estimates and measures proposed.

56. Status of the project as on date shall be submitted along with photographs from North, South, West and East side facing camera and adjoining areas should be provided.

57. Specific location along with dimensions with reference to STP, Parking, Open areas and Green belt etc. should be provided on the layout plan.

58. The DG sets shall be so installed so as to conform to prescribed stack heights and regulations and also to the noise standards as prescribed.

59. E-Waste Management should be done as per MoEF guidelines. Details should be submitted.

Electrical waste should be segregated and disposed suitably as not to impose Environmental Risk.

60. The use of suitably processed plastic waste in the construction of roads should be considered.

61. Displaced persons shall be suitably rehabilitated as per prescribed norms.

62. Dispensary for first aid shall be provided.

63. Safe disposal arrangement of used toiletries items in Hotels should be ensured. Toiletries items could be given complementary to guests, adopting suitable measures.

64. Diesel generating set stacks should be monitored for CO and HC.

65. Ground Water downstream of Rain Water Harvesting pit nearest to STP should be monitored for bacterial contamination. Necessary Hand Pumps should be provided for sampling. The monitoring is to be done both in pre and post monsoon, seasons.

66. The green belt shall consist of 50% trees, 25% shrubs and 25% grass as per MoEF norms.

67. A Separate electric meter shall be provided to monitor consumption of energy for the operation of sewage/effluent treatment in tanks.

68. An energy audit should be annually carried out during the operational phase and submitted to the authority.

69. Project proponents shall endeavor to obtain ISO: 14001 certification. All general and specific conditions mentioned under this environmental clearance should be included in the environmental manual to be prepared for the certification purposes and compliance.

70. Appropriate safety measures should be made for accidental fire.

71. Smoke meters should be installed as warning measures for accidental fires.

b. Specific Conditions:

1. ICEB registration details should be submitted within 3 month.

2. Digging of basement shall be undertaken in view of structural safety of adjacent buildings under information/consultation with District Administration/Mining Department.

3. During the construction phase, a wheel wash arrangement shall be provided at all exit points of the site.

4. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential area. The open spaces inside the plot should be landscaped and covered with grass and shrubs.

(4)