

Registered

State Level Environment Impact Assessment Authority, Uttar Pradesh

Uploaded on
www.seiaaup.in

Directorate of Environment, U.P.

Vineet Khand-1, Gomti Nagar, Lucknow-226 010
Phone : 91-522-2300 541, Fax : 91-522-2300 545
E-mail : docuplko@yahoo.com
Website : www.seiaaup.in, www.seiaaup.com

To,

Mr. Tilak Raj,
General Manager, M/s Supercity Developers Pvt. Ltd.
70, Vikas Marg Extension,
Hargovind Enclave, Delhi-110092.

Ref. No. 913/Praya/SEAC/2308/2013/DD(DS)

Date: 16/09 July, 2015

Sub: Environmental Clearance for Proposed Expansion of Group Housing "Mayfair" at Techzone-IV, Noida Extension, Greater Noida, U.P. by Supercity Developers Pvt. Ltd.

Dear Sir,

Please refer to your application/letter dated 15/05/2014, 17/01/2015, 23/01/2015 and 20/02/2015 addressed to the Director, Environment & Secretary, SEAC, Dr. Bhim Rao Ambedkar Paryavaran Parisar, Vineet Khand-1, Gomti Nagar, Lucknow on the subject as above. The matter was discussed the State Level Expert Appraisal Committee in its meeting held on dated 31/01/2015 and 25/05/2015. A presentation was made by Shri Tilak Raj, authorized representative of the project proponent along with their consultant M/s Ind Tech House Consult. The proponent, through the documents submitted and the presentation made, informed the committee that:

1. The environmental clearance is sought for Expansion of Group Housing Project "MAYFAIR" at Plot No.-7, Techzone-IV, Noida Extension, Greater Noida, U.P. M/s Supercity Developers Pvt. Ltd.
2. Comparative project details of the project is as follows:

Sl. No.	Particulars	As per Approved EC	As per revised proposal	Quantity Change	% Change
1.	Plot Area	24000	24000	0	0
2.	Built Up Area	97631.87	130107.359	32475.50	33.26
3.	Permissible FAR (350 of Plot Area)	66000	84000	18000	27.27
4.	Proposed FAR (349 of Plot Area)	65731.26	83764.66	18033.405	27.44
5.	Total Water Requirement	380	465	85	22.36
6.	Fresh Water Requirement	263	334	71	27.0
7.	Total Waste Water Generation	313	372	59	18.84
8.	STP	380	450	70	18.42
9.	MSW Generation	2116.4	2530	413.6	19.54
10.	Landscape Area Proposed (soft + hard)	13040.364 (hard-3592.852)	13874.9 (hard- 3611)	834.536	6.4
11.	Parking Proposed	1137	1295	158	13.9
12.	Maximum Height of Building	65 m. 56.5 (upto terrace)	56.5 (upto terrace)	No change	No change
13.	Rainwater Harvesting Pits	6	6	0	0

3. Comparative tower wise details is as follows:

Particulars	No. of Floor (As per Approved EC)	No. of Floor (As per Revised Proposal)	Change	Nos. of Units (As per Approved EC)	Nos. of Units (As per Revised Proposal)	Change in No. of DUs
Tower A	S + 18	S + 18	No Change	72	72	No Change
Tower B	S + 18	S + 18	No Change	72	72	No Change
Tower C	S + 18	S + 18	No Change	108	108	No Change
Tower D	S + 18	S + 18	No Change	72	72	No Change
Tower E	S + 18	S + 18	No Change	108	108	No Change
Tower F	S + 18	S + 18	No Change	108	108	No Change
Tower G	S/C + 18	S + 16	+ 02 Floors	90	77	-13
Tower H	S + 10	S + 18	+ 08 Floors	40	72	32
Tower I	S/C + 10	S / C + 18	+ 08 Floors	60	108	48
Tower J	S/C + 10	S / C + 18	+ 08 Floors	40	72	32
Tower K	S/C + 10	S / C + 18	+ 08 Floors	60	108	48
Tower L	S + 9	S + 18	+ 09 Floors	36	72	36
Total				866	1049	183

4. Salient features of the revised proposal is as follows:

Sl. No.	Description	Details	Unit
1	Plot Area	24000	SQM
2	Proposed Built Up Area	130107.359	SQM
3	Cost of The Project	229.0	CR
4	Height of Tallest Tower (upto terrace)	56.5	M
5	Maximum No. of Floors	B+S+18	NOS
6	Permissible Ground Coverage (35%)	8400	SQM
7	Proposed Ground Coverage (25.90%)	6217.19	SQM
8	Permissible FAR (@ 350 of Plot Area)	84000	SQM
9	Proposed FAR (@ 349 of Plot Area)	83765	SQM
10	Stilt Area	3870	SQM
11	Total Basement Area	20334	SQM
12	Ancillary Area	11090	SQM
13	Green Area Required (38.57% of Plot Area)	9258.9	SQM
14	Green Area Proposed (42.76% of Plot Area)	10263.805	SQM

POPULATION & WATER REQUIREMENT			
15	Total No. of DU's (Saleable)	1049	NOS
16	Expected Population	5622	PERSONS
17	Total Water Requirement	465	KLD
18	Fresh Water Requirement	334	KLD
19	Waste Water Generation	372	KLD
20	STP Capacity	450	KLD
21	Treated Water Available for Reuse	298	KLD
22	Surplus Treated Water	167	KLD
RAIN WATER HARVESTING PIT DETAILS			
23	Proposed quantity of rainwater to be harvested	9342	CUM
24	No. of RWH Pits Proposed	6	NOS
PARKING			
25	Parking required as /byelaws	1050	ECS
26	Parking Proposed	1295	ECS
27	Surface Parking	192	ECS
28	Basement Parking	627	ECS
29	Stilt + Podium Parking	476	ECS
WASTE GENERATION			
30	Municipal Solid Waste Generation	2.53	TPD
31	Quantity of E-waste generation	17.04	KG/DAY
32	Quantity of Hazardous Waste Generation	600	LTS/ANNUM
33	Quantity of Sludge generated from STP	134	KG/DAY
POWER REQUIREMENT,			
34	Total Power Requirement (Source-Uttar Pradesh Power Corporation Ltd)	3010	KW
35	DG sets Backup	2200	KVA

5. Water requirement details of the project is as follows:

S. No.	Water Uses	Occupancy/ Capacity/Area	Rate	Total Water Demand (KLD)
A.	Domestic Water Requirement			
(i)	Residential	4975	@86 lpcd	427
(ii)	Non Residential (Employees/ Workers)	149	@30 lpcd	5.0
(iii)	Visitors	497	@12 lpcd	6.0
Total Domestic Water Requirement				438
B.	DG cooling	2200 KVA	@ 0.9 lt/hr/KVA	12.0
C.	Green Area	14024sq m	@ 1 lt/Sq.m.	10.0
D.	Swimming pool (Makeup Water)	1	LS	5
Total Water Requirement				465

6. Source of water supply and its details of the project:

Head	Source	Quantity	UGT	OHT
Fresh Water	Municipal Water	334 KL	220 KL	114 KL

Requirement	Supply (GNIDA)			
Treated Water Requirement	On site STP	131 KL	22 KL (For Gardening & D.G Cooling)	109 KL (For Flushing)
Emergency Water Requirement	Bore well (With permission from CGWA)	-	200 KL	-
Head		Quantity, KL	% w.r.t. Total Water Requirement	
Total Water Requirement		465		
Fresh Water Requirement		334	71.8	
Treated Water Requirement		131	28.17	
Water for Flushing		109		
Gardening		10		
DG Cooling		12		
Waste Water Generation (80% of total domestic fresh water demand + 100% of Flushing Water)		372		
Capacity of STP (120% of Waste Water Generation)		450		
Treated Water Generation		298		
Surplus Treated water (298-131)		167		

7. The project proposals are covered under category 8^a of EIA Notification, 2006, as amended.

Based on the recommendations of the State Level Expert Appraisal Committee Meeting held on 25/05/2015 the State Level Environment Impact Assessment Authority in its Meeting held on 29/06/2015 has decided to grant the Environmental Clearance to the project subject the following specific and general conditions:-

a. Specific Conditions:

1. 03 m peripheral green shall be provided around the project inside the project boundary.
2. 15% area of the total plot area shall be compulsorily made available for the green belt development including the peripheral green belt.
3. Criteria/ norms provided by competent Authority regarding the seismic zone be followed for construction work. Provision of alarm system, to timely notify the residents, in case of occurrence of earthquake/other natural disasters/fire should be provided. A well defined evacuation plan should also be prepared and regular mock drills should be arranged for the residents. Rise of stairs should be constructed in a way, so that it should provide smooth movement.
4. For the treatment for total sewage, a full-fledged STP is to be provided with 20% more capacity than waste water generated during operation phase. 100% waste water is to be treated in captive STP conforming to prescribed standards of receiving body for designated use. Monitoring of STP to be done daily till its stabilization.
5. Dual plumbing should be adopted. Recycling of water as proposed shall be undertaken with regular testing and monitoring of treated water.
6. Dedicated power supply for STPs is to be ensured during operation. Sludge of STP is to be used in-house as manure and surplus manure should be managed by giving it to end users. STP shall be suitably located nearest to back side boundary with shortest out let. Operation and the maintenance cost of the STP shall also be informed along with the compliance of the E-waste and municipal solid waste disposal.

7. Environmental Corporate Responsibility (ECR) plan along with budgetary provision amounting to 2% of total project cost shall be prepared and approved by Board of Directors of the company. A copy of resolution as above shall be submitted to the authority. A list of beneficiaries with their mobile nos./address should be submitted alongwith six monthly compliance reports.
8. LEDs should be used in all common areas and corridors, 100% solar lighting is to be provided in the open areas/ stairs cases.
9. Parking guideline as per Greater Noida Development Authority should be followed. Parking for disabled persons should be explored.
10. All entry/exit point should be bell mouth shaped.
11. To discharge excess treated waste water into public drainage system, permission from the competent authority to be taken prior to any discharge.
12. 100 % provision of Rain Water Harvesting is to be made. RWH shall be initially done only from the roof top. RWH from green and other open areas shall be done only after permission from CGWB.
13. An underground Pucca tank for collection/reuse of rain water may be constructed.
14. Height of the stack should be provided based on combined DG sets capacity and be 6mt higher than the tallest building.
15. Post project monitoring for air, water (surface+ ground), Stack noise of D.G. sets, STP to be carried out as CPCB Guidelines.
16. Crèche to be provided during the construction/operation phase.
17. Provision of separate room for senior citizen with proper amenities shall be made.
18. Protection shall be provided on the windows of the high rise flats for security of residents.
19. Unless and until all the environmental issues are sorted out the occupancy will be restricted and would be only allowed after achieving the Permission from the competent authority.
20. The project proponent shall ensure that the project site does not attract/infringe any buffer zone of no activity identified/declared under law.
21. For any extraction of ground water, prior permission from CGWB shall be taken.
22. Sprinkler to be used for curing and quenching and ready mix concrete may be used for construction.
23. Possibilities of use of treated waste water for irrigation purposes should be explored. Drip irrigation should be tried upto extent possible. No fresh water will be used for irrigation purpose.
24. Mobile toilets, safe drinking water facility, sanitation facility and eco friendly fuels etc. Shall be made available to the temporary residents/workers at the project site including the proper treatment and the disposal of the wastes.
25. The proposal of CSR activity is also be submitted to District Magistrate/Chief Development Officers of District-Gautam Budha Nagar, U.P.

b. General Conditions:

1. It shall be ensured that all standards related to ambient environmental quality and the emission/effluent standards as prescribed by the MoEF are strictly complied with.
2. It shall be ensured that obtain the no objection certificate from the U P pollution control board before start of construction.
3. It shall be ensured that no construction work or preparation of land by the project management except for securing the land is started on the project or the activity without the prior environmental clearance.
4. The proposed land use shall be in accordance to the prescribed land use. A land use certificate issued by the competent Authority shall be obtained in this regards.

5. All trees felling in the project area shall be as permitted by the forest department under the prescribed rules. Suitable clearance in this regard shall be obtained from the competent Authority.
6. Impact of drainage pattern on environment should be provided.
7. Surface hydrology and water regime of the project area within 10 km should be provided.
8. A suitable plan for providing shelter, light and fuel, water and waste disposal for construction labour during the construction phase shall be provided along with the number of proposed workers.
9. Measures shall be undertaken to recycle and reuse treated effluents for horticulture and plantation. A suitable plan for waste water recycling shall be submitted.
10. Obtain proper permission from competent authorities regarding enhanced traffic during and due to construction and operation of project.
11. Obtain necessary clearances from the competent Authority on the abstraction and use of ground water during the construction and operation phases.
12. Hazardous/inflammable/Explosive materials likely to be stored during the construction and operation phases shall be as per standard procedure as prescribed under law. Necessary clearances in this regards shall be obtained.
13. Solid wastes shall be suitably segregated and disposed. A separate and isolated municipal waste collection center should be provided. Necessary plans should be submitted in this regards.
14. Suitable rainwater harvesting systems as per designs of groundwater department shall be installed. Complete proposals in this regard should be submitted.
15. The emissions and effluents etc. from machines, instruments and transport during construction and operation phases should be according to the prescribed standards. Necessary plans in this regard shall be submitted.
16. Water sprinklers and other dust control measures should be undertaken to take care of dust generated during the construction and operation phases. Necessary plans in this regard shall be submitted.
17. Suitable noise abatement measures shall be adopted during the construction and operation phases in order to ensure that the noise emissions do not violate the prescribed ambient noise standards. Necessary plans in this regard shall be submitted.
18. Separate stock piles shall be maintained for excavated top soil and the top soil should be utilized for preparation of green belt.
19. Sewage effluents shall be kept separate from rain water collection and storage system and separately disposed. Other effluents should not be allowed to mix with domestic effluents.
20. Hazardous/Solid wastes generated during construction and operation phases should be disposed off as prescribed under law. Necessary clearances in this regard shall be obtained.
21. Alternate technologies for solid waste disposals (like vermin-culture etc.) should be used in consultation with expert organizations.
22. No wetland should be infringed during construction and operation phases. Any wetland coming in the project area should be suitably rejuvenated and conserved.
23. Pavements shall be so constructed as to allow infiltration of surface run-off of rain water. Fully impermeable pavements shall not be constructed. Construction of pavements around trees shall be as per scientifically accepted principles in order to provide suitable watering, aeration and nutrition to the tree.
24. The Green building Concept suggested by Indian Green Building Council, which is a part of CII-Godrej GBC, shall be studied and followed as far as possible.
25. Compliance with the safety procedures, norms and guidelines as outlined in National Building Code 2005 shall be compulsorily ensured.

26. Ensure usage of dual flush systems for flush cisterns and explore options to use sensor based fixtures, waterless urinals and other water saving techniques.
27. Explore options for use of dual pipe plumbing for use of water with different qualities such as municipal supply, recycled water, ground water etc.
28. Ensure use of measures for reducing water demand for landscaping and using xeriscaping, efficient irrigation equipments & controlled watering systems.
29. Make suitable provisions for using solar energy as alternative source of energy. Solar energy application should be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. Present a detailed report showing how much percentage of backup power for institution can be provided through solar energy so that use and polluting effects of DG sets can be minimized.
30. Make separate provision for segregation, collection, transport and disposal of e-waste.
31. Educate citizens and other stake-holders by putting up hoardings at different places to create environmental awareness.
32. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
33. Prepare and present disaster management plan.
34. A report on the energy conservation measures conforming to energy conservation norms finalized by Bureau of Energy efficiency should be prepared incorporating details about building materials and technology, R & U Factors etc.
35. Fly ash should be used as building material in the construction as per the provision of fly ash notification of September, 1999 and amended as on August, 2003 (The above condition is applicable only if the project lies within 100 km of Thermal Power Station).
36. The DG sets to be used during construction phase should use low sulphur diesel type and should conform to E.P. rules prescribed for air and noise emission standards.
37. Alternate technologies to Chlorination (for disinfection of waste water) including methods like Ultra Violet radiation, Ozonation etc. shall be examined and a report submitted with justification for selected technology.
38. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous variety.
39. The construction of the building and the consequent increased traffic load should be such that the micro climate of the area is not adversely affected.
40. The building should be designed so as to take sufficient safeguards regarding seismic zone sensitivity.
41. High rise buildings should obtain clearance from aviation department of concerned authority.
42. Suitable measures shall be taken to restrain the development of small commercial activities or slums in the vicinity of the complex. All commercial activities should be restricted to special areas earmarked for the purpose.
43. It is suggested that literacy program for weaker sections of society/women/adults (including domestic help) and under privileged children could be provided in a formal way.
44. The use of Compact Fluorescent lamps should be encouraged. A management plan for the safe disposal of used/damaged CFLs should be submitted.
45. It shall be ensured that all Street and park lighting is solar powered. 50% of the same may be provided with dual (solar/electrical) alternatives.

46. Solar water heater shall be installed to the maximum possible capacity. Plans may be drawn up accordingly and submitted with justification.
47. Treated effluents shall be maximally reused to aim for zero discharge. Where ever not possible, a detailed management plan for disposal should be provided with quantities and quality of waste water.
48. The treated effluents should normally not be discharged into public sewers with terminal treatment facilities as they adversely affect the hydraulic capacity of STP. If unable, necessary permission from authorities should be taken.
49. Construction activities including movements of vehicles should be so managed so that no disturbance is caused to nearby residents.
50. All necessary statutory clearances should be obtained and submitted before start of any construction activity and if this condition is violated the clearance, if and when given, shall be automatically deemed to have been cancelled.
51. Parking areas should be in accordance with the norms of MOEF, Government of India. Plans may be drawn up accordingly and submitted.
52. The location of the STP should be such that it is away from human habitation and does not cause problem of odor. Odorless technology options should be examined and a report submitted.
53. The Environment Management plan should also include the break up costs on various activities and the management issues also so that the residents also participate in the implementation of the environment management plan.
54. Detailed plans for safe disposal of STP sludge shall be provided along with ultimate disposal location, quantitative estimates and measures proposed.
55. Status of the project as on date shall be submitted along with photographs from North, South, West and East side facing camera and adjoining areas should be provided.
56. Specific location along with dimensions with reference to STP, Parking, Open areas and Green belt etc. should be provided on the layout plan.
57. The DG sets shall be so installed so as to conform to prescribed stack heights and regulations and also to the noise standards as prescribed. Details should be submitted.
58. E-Waste Management should be done as per MoEF guidelines.
59. Electrical waste should be segregated and disposed suitably as not to impose Environmental Risk.
60. The use of suitably processed plastic waste in the construction of roads should be considered.
61. Displaced persons shall be suitably rehabilitated as per prescribed norms.
62. Dispensary for first aid shall be provided.
63. Safe disposal arrangement of used toiletries items in Hotels should be ensured. Toiletries items could be given complementary to guests, adopting suitable measures.
64. Diesel generating set stacks should be monitored for CO and HC.
65. Ground Water downstream of Rain Water Harvesting pit nearest to STP should be monitored for bacterial contamination. Necessary Hand Pumps should be provided for sampling. The monitoring is to be done both in pre and post monsoon, seasons.
66. The green belt shall consist of 50% trees, 25% shrubs and 25% grass as per MoEF norms.
67. A Separate electric meter shall be provided to monitor consumption of energy for the operation of sewage/effluent treatment in tanks.
68. An energy audit should be annually carried out during the operational phase and submitted to the authority.
69. Project proponents shall endeavor to obtain ISO: 14001 certification. All general and specific conditions mentioned under this environmental clearance should be included in the environmental manual to be prepared for the certification purposes and compliance.

70. Appropriate safety measures should be made for accidental fire.
71. Smoke meters should be installed as warning measures for accidental fires.
72. Project falling within 10 Km. area of Wild Life Sanctuary is to obtain a clearance from National Board Wild Life (NBWL) even if the eco- sensitive zone is not earmarked.

This Environmental Clearance is subject to ownership of the site by the project proponents in confirmation with approved Master Plan for Lucknow. In case of violation, it would not be effective and would automatically be stand cancelled.

You are also directed to ensure that the proposed site is not a part of any no-development zone as required/prescribed/identified under law. In case of violation, this permission shall automatically deem to be cancelled. Also, in the event of any dispute on ownership or land use of the proposed site, this clearance shall automatically deemed to be cancelled.

The project proponent will have to submit approved plans and proposals incorporating the conditions specified in the Environmental Clearance within 03 months of issue of the clearance. The SEIAA/MoEF reserves the right to revoke the environmental clearance, if conditions stipulated are not implemented to the satisfaction of SEIAA/MoEF. SEIAA may impose additional environmental conditions or modify the existing ones, if necessary. Necessary statutory clearances should be obtained and submitted before start of any construction activity.

These stipulations would be enforced among others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006 including the amendments and rules made thereafter.

This is to request you to take further necessary action in the matter as per provision of Gazette Notification No. S.O. 1533(E) dated 14.9.2006, as amended and send half yearly compliance reports in respect of the stipulated prior environmental clearance terms and conditions in hard and soft copies to the SEIAA, U.P. on 1st June and 1st December of each calendar year.




(J. S. Yadav)
Member Secretary, SEIAA

Ref. No...../Praya/SEAC/2308/2014/AD(VB) Dated

Copy with enclosure for Information and necessary action to:

1. The Principal Secretary, Department of Environment, Govt. of Uttar Pradesh, Lucknow.
2. Advisor, IA Division, Ministry of Environment & Forests, Govt. of India, Indira Paryavaran Bhawan, Jor Bagh Road, Aliganj, New Delhi-110003.
3. Chief Conservator, Regional Office, Ministry of Environment & Forests, (Central Region), Kendriya Bhawan, 5th Floor, Sector-H, Aliganj, Lucknow.
4. District Magistrate, Gautam Budha Nagar, U.P.
5. The Member Secretary, U.P. Pollution Control Board, TC-12V, Vibhuti Khand, Gomti Nagar, Lucknow.
6. Copy to Web Master/ guard file.



(Dr. A.A. Khan)
OST(T)/Nodal Officer,
SEIAA