

DEVELOPMENT WORKS	BRIEF DESCRIPTION
Demarcation of plots	We have one plot of size 2509.293 sq. mtr.having 1 main entrance gate from the 9 m wide front road.
Boundry wall	1 m high and 115 mm thick Brick work
Road work	From the main entrance gate we have 80 mm thick brick road through out the project. Whose wideness starts from 9 mtr.
Water supply including drinking water supply	We will provide underground pipelines for water
Sewer system	Main sever line will connect all the plots which will further drain to septick tank
Drain	Storm water shall be Provided. Storm water from Roads and other landscape area shall be connect to the Storm water drain channel and go to the Rain water harvesting Pit for recharge the Ground water and overflow shall be connect with Municipal drain line.
Tree planting	We will provide many type of trees all along the internal road
Design for electric supply including street lighting	We will design & implement the system as per local electricity Board.
Treatment and Disposal System of Sewage and Sullage water	All sewage water shall go to septic tank pit and overflow from septic tank shall be connected with municipal sewage system,when come in to force.
Solid Waste Management And Disposal System	Solild waste will be collected at garbage collection area provided for in the project