SPECIFICATION	
DEVELOPMENT WORK NAME	BRIEF DESCRIPTION
Demarcation of Plots	The plots will be demarcated by concrete/brick pillars to all four sides of the Plot Boundary, to the exact shape, size and orientation as per sanctioned map by Lucknow Development Authority.
Project Boundary	A 2.4 meter high pre-fabricated boundary wall will be constructed with deep foundation along with barbed wire boundary fencing at the top.
Road Work	Bitumen/RCC Road wherever applicable as per approved layout.
Footpaths	Combination Green / Paver blocks
Water Supply	Portable water by Underground Tank.
Sewer System	Sewage will be collected through a RCC Hume pipe arrangement, leading to Sewerage Treatment Plant.
Drain	Surface drain water will be collected through RCC pipe and will be released to Storm Water Line for discharge.
Parks	The green areas will be landscaped with hard and soft landscaping as per design. The parks will have footpaths, sitting area and play area for children.
Tree Plantation	The trees will be planted at all suitable locations of the project and along the boundary wall.
Electric Supply & Street Light	Electrical layout and capacity will be installed to suffice the domestic use. All electrical cabling will be underground and street lights will be as per working drawings.