

DEVELOPMENT WORKS	BRIEF DESCRIPTION
Demarcation of plots	Project consists of 97 plots
Boundry wall	Peripherial compound wall comprising of foundation and 1.5m high masonry wall with barbed wire fencing including plastering and painting as per design.
Road work	We have road netwrok varying from 9m to 18 m. All roads are bituminous/asphalt roads in the project.
Footpaths	In this project internal footpaths will not be provided.
Water supply including drinking water supply	We will provide water tanks with adequate distribution mechanism and connection through underground pipelines.
Sewer system	Modular Sewerage system is planned which shall be connected with the Municipal sewerage system.
Drain	Storm water shall be Provided. Storm water from Roads and other landscape area shall be connect to the Storm water drain channel and overflow shall be connect with Municipal drain line.
Parks	We will provide green area with the different activities spread across approx 5,000 sq.m
Tree planting	We will provide many type of trees with diverse fauna and various species all along the project.
Design for eletric supply including street lighting	We will design & implement the system as per local electricity Board .
Treatment and Disposal System of Sewage and Sullage water	Modular Sewerage system is planned which shall be connected with the Municipal sewerage system.
Solid Waste Management And Disposal System	There is adequate garbage collection area provided for the solid waste management.
Water Conservation System	We shall provide rain water harvesting system for water conservation and improve the ground water level.