

**(Schedule-G)**

**ALLAHABAD DEVELOPMENT AUTHORITY, ALLAHABAD**

**BILL OF QUANTITY**

NAME OF WORK. : Development Work of Arazi No.32, 32-1 & 32-2 at Chak Babura, Alimabad, Naini, Allahabad..

DATE OF TENDER : .09.2016

COST OF TENDER : Rs. 00

EARNEST MONEY : Rs. \_\_\_\_\_.00

TIME OF COMPLETION : \_\_\_\_\_

| Sl. No.    | Particulars   | Qty.   | Unit | Rate    |
|------------|---|--------|------|---------|
| 1          | Earth work in cutting in embankment in ordinary soil excavation to be in the form of regular pits not exceeding 0.50 M in depth and earth work in embankment to be in 20cm layers including ramming & dressing the surface to required level & slopes and also including 1.50M lift and 30 M lead the earth from cutting to be used in making embankment or to be deposited as spoil bank within 30 Mtr. distance as directed by E/I. | 360.00 | Cum  | 122.00  |
| 2          | Cartage of earth up to 5.0 Km distance all complete.  | 360.00 | Cum  | 159.65  |
| Nali       |   |        |      |         |
| 3          | Earth work in excavation in foundation in Kankar mix soil all complete.   | 56.00  | Cum  | 160.00  |
| 4          | D/L C.C. 12:6:1 with 40 mm B/B all complete.  | 23.00  | Cum  | 2795.00 |
| 5          | Class M-150 Brick work in 1:4 (1 Cement & four coarse sand in foundation including supply of all materials, labour & tools & plants etc. required for proper completion of work.  | 69.00  | Cum  | 5200.00 |
| 6          | Struck pointing with cement mortar consisting 1:2 cement and fine sand of 1.25 FM including supply and all material labour T&P etc. respect for proper completion of work.  | 280.00 | Sqm  | 160.00  |
| 7          | RCC in raft foundation in 1:1.5:3 with cement approved coarse sand and 2cm gauge approved stone grit excluding supply of reinforcement and its bending but including its fixing and binding the same with 24 B.W.G.G.I. Binding wire and including necessary centering and shuttering etc. and supply of all materials, labour T&P etc. required for proper completion as per direction of E/I.                                       | 4.00   | Cum  | 8300.00 |
| 8          | M.S. or Iron work in angle iron door and window frame including cutting, welding and wastage including supply of all material, labour T&P etc. required for proper completion of the work, etc all complete.  | 4.71   | Qtl. | 6900.00 |
| Sewer Line |   |        |      |         |
| 1          | Earth work in excavation from drain in foul condition including all complete.   | 120.00 | Cum  | 140.00  |
| 2          | D/L C.C. 8:4:1 with 40 mm B/B all complete.   | 12.00  | Cum  | 3000.00 |

all comp. 18.2x200x0.70x0.08 = 22.40 M<sup>3</sup>

आगे ले जाया गया