

SCHEDULE 'D' AND SCHEDULE 'E'
Specifications, Amenities, facilities
(SUBJECT TO MINOR VARIATION AS PER AVAILABILITY)

| | | | |
|----|------------------------|----------|---|
| 1 | Structure | | Earthquake Resistance R.C.C Frame Structure |
| 2 | Rooms | Flooring | Vitrified Tiles |
| 3 | Kitchen | Flooring | Ceramic Tiles (Anti-Skid) |
| | | Wall | Ceramic Tiles up-to 2'-0" HT. above the Counter and Oil Bound Distemper in Balance Area |
| 4 | Toilet and Bathroom | Flooring | Anti-Skid Ceramic Tiles |
| | | Wall | Ceramic Tiles up-to 7'-0" HT. |
| 5 | Common Area | Flooring | Ceramic Tiles |
| 6 | Staircase | Flooring | Granite/ Vitrified Tiles |
| 7 | Door / Window | | External UPVC Door and window with 5mm Toughened Glass |
| | | | Internal door Frames of marandi |
| | | | Flush door shutter with laminate |
| | | Fittings | ISI Marked Standard Fittings & Locks |
| 8 | Plumbing | | PVC/CPVC Pipe for Plumbing Piping Works |
| | | | C.P Fittings |
| | | | Stainless Steel Sink in Kitchen |
| 9 | Interior Sanitary Work | | Low Level PVC Cistern with European Toilet Seat in first Toilet |
| | | | Low Level PVC Cistern with European Toilet Seat |
| 10 | Electrical | | Fire Resistant I.S.I Mark Wiring |
| | | | Modular Switches and Sockets as per ISI Standard |
| | | | All Materials as per ISI Standard |
| 11 | Finishing | | Weather Coat Finishing on Outside Walls |
| | | | Oil Bound Distemper Inside |

These specifications are only indicative and are likely to be changed on professional advice / Public demand etc. or due to changes as suggested by the architect or any other competent Government agency.

FOR SHREE SAI BABA INFRA PROJECT PVT LTD

Shree Saibaba Infraprojects (P) Ltd.
 (Director)

Director

Registered Office : HIG-5, Phase-2, Ashok Vihar Colony, Pahariya, Varanasi
 T: +91 0542 2500657 E: ssbinfraproject@gmail.com,
 info@ssbinfraproject.com W: ssbinfraproject.com
 Tollfree Number: 180030008255