(Schedule-G)

ALLAHABAD DEVELOPMENT AUTHORITY, ALLAHABAD

BILL OF QUANTITY

NAME OF WORK

Constrution & Development Work of EWS (G+3) 312 Flats under PMAY in Sector Gokul at Kalindipuram Housing

Scheme, Allahabad.

DATE OF TENDER

26.02.2018

EARNEST MONEY
TIME OF COLUMN

5600/-

69.00 Lac

TIME OF COMPLETION:

18 Months

SI. NO	Particular of Item	Qty	Unit	Rate
	Part-A : Building Work			
	Civil Work			
1	Excavation in foundation in ordinary soil (loam clay or sand) including lift upto 1.50 metre and lead upto 30 mtr. including filling watering and ramming of excavated earth into the trenches or into the space between the building and the sides of foundation, trenches or into the plinth and removal & disposal of surplus earth as directed by the Engineer in-charge upto a distance of 30m from the foundation trenches. (SOR SI.No. 251/2015)	3080.00	Cum	140.00
2	Earth work in cutting in embankment in ordinary soil excavation to be in the form of regular pits not exceeding 0.50 M in depth and earth work in embankment to be in 20cm layers including ramming & dressing the surface to required level & slopes and also including 1.50M lift and 30 M lead the earth from cutting to be used in making embankment or to be deposited as spoil bank within 30 Mtr. distance as directed by E/I. 5.00 Km cartage as per directed of E/I. (SOR SI.No. 253+231a/2015)	2202.00	Cum	281.65
3	Sand filling in plinth including supply of necessary quantity of sand to the site of work and including watering ramming consolidating and dressing complete etc. labour and T&P etc. required for the proper completion of the work. Lead 50 M and lift up to 1.50 M. (PWD Chapter-1 SI.No. 6A/2015)	325.00	Cum	475.00
4	Cement Concrete with 40 mm gauge approved stone ballast, coarse sand and cement in proportions of 8:4:1 including supply of all materials, labour, T&P etc. required for proper completion of all work. (SOR SI.No. 281/2015)	538.85	Cum	4236.35
5	RCC in raft foundation and footing in the proportions 1:1.5:3 in cement approved coarse sand and 4cm gauge approved stone ballast excluding supply of reinforcement and its bending but excluding its fixing and binding the same with 24 B.W.G.G.I. Binding wire and including necessary centering and shuttering etc. and supply of all materials, labour T&P etc. required for proper completion as per direction of E/I. (SOR SI.No. 287+285-284/2015)	656.50	Cum	5757.30
6	M.S. or Iron work in Plain work such as RCC or R.B. work including bending for proper shape and including supply of steel & its wastage bend, hooks and authorized overlapping shall be measured and including cost of binding wire. (SOR SI.No. 504/2015)	780.00	Qtl.	5711.00