

DEVELOPMENT WORKS	BRIEF DESCRIPTION
Demarcation of plots	We have one plot of size 4413 sq. mtr. having 1 main entrance gate
Boundry wall	1.5 mt high boundary wall will be there in the project. At the center face of boundary wall there would be a Logo of the project which give a beautiful iconic design to boundary wall.
Road work	There will be interlocking brick/RCC road throughout the project with thickness of 300 mm.
Footpaths	We will provide footpath with width of 1.5 mt and thickness of 60mm in the project.
Water supply including drinking water supply	We will provide One pump for the requirement of blocks through underground pipelines.
Sewer system	Modular Sewerage system shall be Provided. All Sewerage water shall be go to the STP and overflow from the STP shall be connect with the Municipal sewerage system.when come into force.
Drain	Storm water shall be Provided. Storm water from Roads and other landscape area shall be connect to the Storm water drain channel and go to the Rain water harvesting Pit for recharge the Ground water and overflow shall be connect with Municipal drain line.
Parks	We will provide green area with the different activities and the green area will have gaming facilities for kids.
Tree planting	We will provide many type of trees all along the boundary wall & green area
Design for eletric supply including street lighting	We will design & implement the system as per local electricity Board and will consider centralized Transformer, HT panel, LT Panel, Feeder Pillar and DG back for common service like External lighting, Fountain, STP, Pump room etc.
Treatment and Disposal System of Sewage and Sullage water	Modular Sewerage system shall be Provided. All Sewerage water shall be go to the STP and overflow from the STP shall be connect with the Municipal sewerage system.,when come into force.
Solid Waste Management And Disposal System	There are a proper garbage collection area provided for the solid waste management.
Water Conservation System	We will suggest to individual to use low flow fixtures as well dual flush cistern and raw water harvesting system to reduce the water consumption and improve the ground water level.