

Specifications

Annexure - 9 E

“Assotech Business Cresterra- Phase -2” (Ongoing Project)

S. No.	Area	Specification
1	Common Area	
	Flooring	Vitrified Tiles
	Wall Finishing	OBD
	Stairs	Marble Stone / Kota Stone
2	Shops (Internal)	
	Flooring	No Flooring
	Wall Finishing	Plastered with Primer Coat
	Ceiling	No False Ceiling
3	Toilets	
	Flooring	Antiskid Ceramic Tiles
	Counter	Granite or Equivalent
	Wall Finishing	Ceramic Tiles Dado and balance Plastered with OBD
	Fittings	Washbasin, WC, CP Fittings, Mirror etc of standard brands.
	Others	Flush Door shutter
4	Shutter	M S Rolling Shutter for Shops
5	Electrical	PVC Concealed conduits, Copper wiring upto Distribution Box inside Shop, Distribution Box with Protective MCB to be provided inside Shop, Provision for Telephone point, Ceiling mounted light fittings in common area only
6	Power Back Up	100% Power Back up for shops and offices
7	Security & Fire Fighting	24 x 7 Security with CCTV Cameras, Alarm and Fire fighting system

Note : Assotech Business Cresterra - Phase - 2, being ongoing project. Please refer to special notes to the application for registration of RER