Project Specifications

SVING / DINING / LOBSY

Floor: 2'-0"x2'-0" vitrified tiles
Walls: POP base with OBD finish
Celling: POP base with OBD finish

BED ROOM

Hoor: 2'-0"x2'-0" vitrified tiles Walls: POP base with OBD finish Calling: POP base with OBD finish

KITCHEN

Floor: Ceramic tiles
Walls: Ceramic tiles dado upto 2'-0" above
counter

Counter: Granite top CP Fittings
Laquar/equivalent, statisless steel sink
fixture exhaust, mixer, grinder, water purifier
electrical points etc.

110

Walls: ceramic tiles dado up to 7'-0" height CP fittings /: Jaquar / equivalentFixture Sanitary ware: Good quality ISI marked sanitary fittings.

Celling: POP base with OBD finish

BALCONY

Floor: Anti skid ceramic tiles
Walls: Weather coat paint
Ceiling: POP base with OBD finish

DOOR

Hard wood frame work, main door teak wood good quality flush door in remaining rooms / toilet / kitchen / balcony.

WINDOW

Painted hard wood frame and fully glazed shutters with MS grill and powder coated fittings.

ELECTRIC WORK

Copper wire, modular switches & sockets of ISI marked AC point with wiring in drawing, bed rooms.

STAIRS

MS railing with MS Handrail, granite flooring.

STRUCTURE

Earthquake resistant RCC framed structure, designed by qualified structural engineer.

Floor: Ceramic tiles

Walls: Ceramic tiles dado upto 2'-0" above

counter

Counter: Granite topCP Fittings /:

Jaquar/equivalent, stainless steel sink, fixture exhaust, mixer, grinder, water purifier electrical points etc.