

Project Specifications:

- 1.Roads: Pavement quality concrete roads in trimix finish, with interlocking paver- tiles in pathways, on both sides as per layout plan.
- 2.Sewers: Concrete Hume Pipes. Manholes in brick masonry plastered inside. Discharge to STP in township.
- 3.Drains: Concrete Hume Pipes with Catch basins and Chambers in Brick Masonry. Outfall to external municipal trunk discharge line.
- 4.Water Supply: Source Municipal supply Through UGT/OHSR (in Township).
- 5.External Electrification: Underground transmission - Cabled HT and LT routes along road embankments to transformers and thereafter street side feeder pillars for individual domestic connections.
- 6.Power Connectivity from (external) Sub-Station in township. Power Supply from KESCO.
- 7.Street and Park Lighting: Electric poles as per layout.
- 8.MSW: Door to door collection in go-carts / cycle rickshaws by facility manager/RWA, and Disposal at Center provided in township.
- 9.Parks: Landscaped parks and play areas as per layout plan.