


PROJECT SPECIFICATIONS
PROJECT: SHRI RADHA GULMOHAR-4

SN	SERVICES	SPECIFICATION
1	Demarcation of the Plot.	Demarcation of plot line with prefabricated RCC muddy on all four corner of plots.
2	Drainage & Sewer Line.	Laying of DWC /RCC pipes and making of Manhole by Civil masonry Work.
3	Electricity Line & Transfers.	Laying of overhead HT and LT cables , Erection of poles with provision of required capacity transformers as per UPPCL Guidelines.
4	Water Supply	Laying of DWC pipes of required dia as per MEP designs and making of manholes of required size.
5	Road	laying of pavers over well compacted subgrade with GSB layers.
6	Sewage Treatment Plant.	Construction of STP collection tank along with modular treatment system,as per MEP drawings.
7	Pump house.	Filling by summerceible for the UGT
8	Boundary walls	230 mm Wall in brick masonry with FPS bricks of class designation 75 in ratio of 1:6 cement mortar on RCC footing and colum structure.
9	landscaped areas and gardens.	Landscape and gardnes as per consultant drawings
10	Rain Water Harvesting	Making of Rain Water Harvesting pits to filter rainwater of required capacity as per MEP designs

For SJP Global Limited

 Authorised Signatory

S.J.P. Global Ltd.

Corporate Office A-133, Sector 63, NOIDA 201301
 HQ 111, SHRI Jamuna Dham, Goverdhan Road, Mathura 281004
www.SHRIGROUP.co

T +91 120 4919999 F +91 120 4254544
 T +91 565 2425038 F +91 565 2425051
info@shrigroup.net