



Tripurari Estate Private Limited Pushpanjali Mandapam Project Specification

S.No.	Type of Work	Specification
1	Demarcation of Plots	<u>Plots In Sq Mtr.</u> 0-100 (27), & Commercial Plot (1) Area 93.06 Sq. Mtr (Total 28 Plots Including 1 Commercial Plots)
2	Road Construction	WBM with Tremix
3	Park Boundary	3feet Park Boundary with Brick work, Plaster work and paint work
4	Drain K.C. and Sewar	Diging, brick work and plaster
5	Sewage Treatment Plan	Underground sever line 6"inch with PVC pipe (6kg approx), mainhole and as per according to drawing
6	Water Line	4" UPVC Water Line with underground tank
7	Electrification	Electric Poll & Street Light, Transformers for Light
8	Park Gate	3feet Iron Gate
9	Dalab Ghar	Dalab Ghar as per drawing
10	Rain Water Harvesting	8x10x6 feet well with brick work and 6"inch boaring upto water level as per drawing
11	Boundary Wall of Site	8 Feet height brick work, plaster with entry gate
12	Plant and Greenry	Grass in park and innering hadge and permanent plants, with shade plants

