

## PROJECT SPECIFICATIONS

Demarcation of Plots	Demarcation of plots will be done according to the sanctioned plan using brick pillars.
Boundary Wall	Boundary of the Project Site is constructed using precast concrete panels and posts.
Road Work	Required thickness of bitumen coating with seal coat over the intermediate base over which sub-base will be done in the metalled portion.
Footpath	Pathways will be made using paver blocks/ interlocking tiles, etc.
Water Supply Including Drinking Water Facilities	An overhead water tank of 100 KL capacity is under construction. The water from there will be delivered through an underground PVC Pipe Line.
Sewer System	Sewage will be collected through RCC Hume pipe arrangement as per Sewer Plan.
Drain	Surface drain will be laid on lean concrete bed on compacted earth in required size with brickwork.
Parks	Lush green park will be maintained in the project as per the sanctioned plan.
Tree Planting	The trees will be planted at all suitable locations of the project. The tree selections will be done to ensure no hindrances in the services in future.
Design For Electric including Lighting	Electrical supply with HT & LT panels using suitable electric cabling in the project premises as per the requirements of the electricity department.
Treatment and Disposal System of Sewage and Sullage Water	As per the Sewer Plan.
Solid Waste Management and Disposal System	Dustbins and garbage disposal areas for solid waste management will be provided.
Water Conservation System	Rain Water harvesting system will be constructed.